



A Tradition of Stewardship
A Commitment to Service

Department of Public Works

1195 Third Street, Suite 101
Napa, CA 94559-3092
www.countyofnapa.org

Main: (707) 253-4351
Fax: (707) 253-4627

Steven Lederer
Director of Public Works

June 1, 2020

RE: Dry Creek 10.75 MSE Wall, RDS 19-14

Dear Sir/Madam,

Enclosed here within is Addendum Number 1 for the above referenced project. This Addendum Number 1 forms a part of the proposal documents, modifies the original plans/specifications **and shall be acknowledged in the Addendum Acknowledgement page of the proposal forms.** All other conditions remain the same.

ADDENDUM NUMBER 1

Item 1 – P-2, PROPOSAL FORM P-2

DELETE:

The entire page P-2

INSERT:

The entire page P-2 shown on the next page.

Note that changes have been highlighted in bold and underlined. Contract pages will be updated with actual bid cost and total to match the proposal after award.

DRY CREEK 10.75 MSE WALL, RDS 19-14

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
A. GENERAL CONDITION					
1	Mobilization	LS	1		
2	Clearing And Grubbing	LS	1		
3	Traffic Control	LS	1		
4	Erosion And Sediment Control, Check Dam, etc...	LS	1		
5	Miscellaneous	LS	1		
B. ROADWAY EXCAVATION, GRADING AND DRAINAGE, MISC ITEMS					
6	Roadway Excavation, Pavement Grinding (<u>2 inch</u>), Offhaul of Surplus Rock & Soil	LS	1		
7	Sawcut	LF	48		
8	Hot Mix Asphalt (Type A) with Fiber	TON	68		
9	Class 2 Aggregate Base	CY	60		
10	MGS Type A77P2 with Terminal Ends & Reflectors	LS	1		
11	Cable Railing System	LS	1		
12	4" Thermoplastic Traffic Stripe (Caltrans Detail 21)	LF	170		
13	Caltrans Type G1 Inlets with Aprons, D= 6'	LS	<u>2</u>		
14	18" Storm Drain Removal and Replacement	<u>LS</u>	<u>1</u>		
15	Rock Slope Protection, Class 111, 150 lb., Method B	CY	7		
16	Type F AC Dike, Caltrans A87B	LF	90		
C. RETAINING WALL					
17	Structure Excavation	CY	379		
18	Imported Structure Backfill	CY	347		
19	Pervious Backfill	CY	51		
20	Structural Wall	SF	850		
21	Mirafi 140N (or equal)	<u>SF</u>	<u>3,740</u>		
22	Minor Concrete	CY	6		
23	Geogrid, Vers-Grid SVG, Mirafi 3XT	SF	6,545		
24	Sleeve-IT™, ISO 1224R	EA	10		
25	<u>4" Perforated Pipe</u>	<u>LF</u>	<u>300</u>		
TOTAL BASE BID					
TOTAL BASE BID (WRITTEN)					


END OF ADDENDUM NUMBER 1

Thank you for your interest in this project. If you have any questions relating to this correspondence, please e-mail Frank.Lucido@countyofnapa.org.

Sincerely Yours,

Steve Lederer
Director of Public Works

By:

A handwritten signature in blue ink, appearing to read "Frank Lucido", is written over a horizontal line.

Frank Lucido, P.E.
Engineering Manager