

STEELE CANYON ROAD MPM 2.0 LNU FIRE EMERGENCY REPAIR

<p align="center">STEELE CANYON RD MPM 2.0, RDS 20-42 2020 FIRE DAMAGE REPAIR CULVERT REPLACEMENT</p>					
<p align="center">AGENCY: COUNTY OF NAPA</p>					
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
A. GENERAL CONDITION					
1	Mobilization	LS	1		
2	Clearing And Grubbing	LS	1		
3	Traffic Control	LS	1		
4	Water Pollution Control	LS	1		
B. ROADWAY/GULLY EXCAVATION, GRADING, CULVERT AND MISC ITEMS					
1F	Excavation/Grading (at Gully and Pipe Trench)	CY	68		
2	Sawcut	LF	60		
3	Remove and Dipose of Existing AC Pavement	CY	2		
4	Remove Existing 30" HDPE Pipe	LF	15		
5	Hot Mix Asphalt (Type A)	TON	1.0		
6	Offhaul Soil (Surplus Material)	CY	43		
7	Lean Concrete (Trench Backfill)	CY	10		
8	30" CMP (w/ Anchor, Stakes and Couplings)	LF	187		
9	6" PVC (Solid)	LF	100		
10	Metal Flared End Section	EA	1		
11	Concrete Headwall	EA	1		
12	RSP Fabric (Mirafi 500X)	SF	945		
13	RSP	TON	60		
14	4" Thermoplastic Traffic Stripe (Caltrans Std. Plan Detail 21)	LF	4.5		
TOTAL BASE BID					
TOTAL BASE BID (WRITTEN)					

'F' Denotes Final Pay Items

Bids are required for the entire work. In order to maximize construction within the funding available to the County, the following procedure will be used: The lowest bid shall be determined in a manner that benefits the County and brings the extents of the project to or below the budget amount the County can spend on this project. The award of contract, if awarded, shall be based on budget requirements and shall be made to the lowest responsible responsive bidder. The lowest bid shall be to the lowest of the bid prices on the Base Bid.