



A Tradition of Stewardship
A Commitment to Service

Department of Public Works

1195 Third Street, Suite 101

Napa, CA 94559-3092

www.countyofnapa.org/publicworks

Main: (707) 253-4351

Fax: (707) 253-4627

Steven E. Lederer

Director of Public Works

January 29, 2020

Via Email to Plan Holders, Contractors and Builders Exchanges

**RE: STEELE CANYON ROAD MPM 2.0, RDS 20-42, 2020 FIRE DAMAGE REPAIR,
CULVERT REPLACEMENT - ADDENDUM 1**

Dear Prospective Bidders:

Enclosed herein is Addendum number 1 for the above referenced project. Addendum No. 1 forms a part of the contract documents, and modifies OR clarifies the original plans and specifications and shall be acknowledged in the Addendum Acknowledgement page. **All other conditions remain the same.**

ADDENDUM NUMBER 1 (Total number of pages including this page: 2 Pages)

1. The plan set (sheet 1 of 1) is replaced in its entirety with the Revision Cloud/Delta 1 shown.
2. Page 'P-6' of the Proposal Form is replaced in its entirety.
3. Page "C-2" of the Construction Contract is replaced in its entirety.

Response to Bidders' Questions:

Question#1: Can the headwall be cast-in-place inn lieu of pre-cast?

Answer#1: Yes, the revised plan no longer requires 'pre-cast' due to a long lead time and the headwall should be 'cast-in-place'. The bid unit price is a lump sum for one headwall per Caltrans Standard Detail D89B. Please note that per the note on the revised plan, the required distance between the top of the 30" CMP to the top of the headwall is 9 inches.

Question#2: What is the extent of excavation required at the gully.

Answer#2: The length of the gully is approximately 65 linear feet. The excavation is approximately 4 feet deep and the width is between 4-6 feet.

Question#3: Is a cable anchor system per Caltrans D87C required to anchor the pipe on the side of the slope?

Answer#3: No but 1 ½ inch stakes (6 feet long) are required per Caltrans Standard D87A

Question#4: Does the work need to be completed by October 15?

MANLEY LANE (LOP 235) AND THIRD AVE (LOP 208 AND 209) – ADDENDUM NO. 1

Answer#4: The project is scheduled to begin work in early October 2020 and the contractor shall have 15 working days to finish the project. The exact start date will be determined depending on when the contract can be signed and executed. Since the rain season is approaching, the County would like to finish this project as soon as feasible.

Question#5: *Can you confirm that the Good Faith Effort requirements for this project are all due at the time of the bid? Will there be an extension for these documents to be turned in after the bid?*

Answer#5: The Exhibit B “DBE Subcontractor Utilization Form’ is required at the time when the bid is submitted. The Good Faith Effort documents are required to submit to the County within five working days after the bid.

END ADDENDUM NUMBER 1

Please complete the Addendum Acknowledgement form in the Proposal Form acknowledging receipt of this addendum.

Thank you for your interest in this project. If you have any questions regarding this addendum, please feel free to contact Dewey Phan (Dewey.Phan@countyofnapa.org) at Napa County Public Works, 1195 Third St. Suite 101, Napa, CA 94559, Fax # 707- 253-4627.

Sincerely Yours,
STEVEN E. LEDERER
Director of Public Works

By: 
Dewey Phan
Project Engineer