

2020 LNU FIRE FHWA GUARDRAIL REPLACEMENT PROJECT, RDS 20-40					
AGENCY: COUNTY OF NAPA					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
A. GENERAL CONDITION					
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Guardrail Removal	LS	1		
B. BERRYESSA-KNOXVILLE ROAD					
1	MGS A77L2 (Steel Post and Plastic Blocks)	LF	5069		
2	MGS Terminal System A77P2 (Type MSKT)	EA	20		
3	MGS Terminal System A77P2 (Type SRT)	EA	6		
4	Replace 168 Damaged Plastic Blocks	LS	1		
5	Replace Individual Rail Segment Only	EA	6		
6	MGS Buried Post End Anchor A77T2	EA	4		
C. POPE CANYON ROAD					
1	MGS A77L2 (Steel Post and Plastic Block)	LF	9581		
2	Connect to Existing Guardrail	EA	1		
3	MGS Terminal System A77P2 (Type MSKT)	EA	19		
4	MGS Terminal System A77P2 (Type SRT)	EA	2		
5	MGS A77Q4 Type 12BB Structure Departure	EA	2		
6	MGS A77Q1 Type 12B Structure Approach	EA	2		
7	MGS Buried Post End Anchor A77T2	EA	8		
D. BUTTS CANYON ROAD					
1	MGS A77L2 (Steel Post and Plastic Block)	LF	399		
2	MGS Terminal System A77N6 (Type MSKT)	EA	8		
3	MGS A77Q4 Type 12BB Structure Departure	EA	2		
4	MGS A77Q1 Type 12B Structure Approach	EA	2		
TOTAL BASE BID					
TOTAL BASE BID (WRITTEN)					